BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: Improvements to Road at Chikkasandra near Sapthagiri College area, in Shettyhalli Sub Division, Ward No-12.

Sl. No	Description of work	Unit	Qty	Sanctioned Estimate Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods Complete as per Specifications.	Cum	288.00	151.74	Rupees One Hundred Fifty One and Sevent Four Paise Onl
2	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 kgs, using 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregate @ 0.465cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing Complete as per Specifications.	Cum	36.00	4497.12	Rupees Four Thousand Fou Hundred Ninet Seven and Twelve Paise Only
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20 mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase lintels retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing Complete as per Specifications.	Cum	87.00	5639.76	Rupees Five Thousand Six Hundred Thirty Nine and Seventy Six Paise Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per Specifications.	Qtls	52.20	7380.72	Rupees Seven Thousand Thre Hundred Eight and Seventy Tw Paise Only

Signature of Measurement

Technical Manager (TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer

1	2	3	4	5	6
5	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor, cills, plinth including cost of all materials, labour Complete as per Specifications.	Sqm	800.00	666.36	Rupees Six Hundred Sixty Six and Thirty Six Paise Only
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	180.00	1963.60	Rupees One Thousand Nine Hundred Sixty Three and Sixty Paise Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Complete as per Specifications.	Cum	231.00	94.82	Rupees Ninety Four and Eighty Two Paise Only

Signature of the Contractor

Technical Manager (TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer,
Dasarahalli Division,